


### The GUINEVERE-project at VENUS

P. Baeten, H. Aït Abderrahim, G. Vittiglio, B. Verboomen, G. Bergmans, F. Vermeersch

On behalf of the ECATS community



#### Structure of IP-EUROTRANS



DM3 AFTRA Fuels F. Delage, CEA DM4 DEMETRA
HLM Technologies
C. Fazio, FZK

DM5 NUDATRA
Nuclear Data
E. Gonzalez,
CIEMAT



### Objectives of DM2 ECATS

- Qualification of sub-criticality monitoring,
- > Validation of the core power / beam current relationship,
- > Start-up and shut-down procedures, instrumentation validation and specific dedicated experimentation,
- Interpretation and validation of experimental data, benchmarking and code validation activities etc.,
- Safety and licensing issues of different component parts as well as that of the integrated system as a whole.
- Validation of generic dynamic behaviour of an ADS in a wide range of sub-critical levels, sub-criticality safety margins and thermal feedback effects,
- Extend and complete the MUSE-experiments (CEA, Cadarache)

(pulsed GENEPI at sodium fast reactor MASURCA)




## GUINEVERE Objective

- Perform a (low-power) coupling experiment:
  - > With a continuous beam
    - \* Beam interruptions
    - \* Pulsed experiments
  - Implement all together the individual techniques tested in MUSE => sub-criticality monitoring
  - > With a fast subcritical lead multiplying system
    - \* Reference to a critical state
- Use of the VENUS installation and coupling to GENEPI



## Modifications: VENUS Today

## VENUS is a very flexible water moderated zero power facility used for accurate measurement in view of code validation








#### VENUS Needed Modifications

- Coupling of the GENEPI accelerator to the subcritical reactor VENUS will imply the adaptation of the current infrastructure to host GFNFPI
  - > A coupling with a 14 MeV neutron generator has already been performed at VENUS in the 60's
- To modify the water-moderated reactor in a solid lead reactor, the following main items were identified:
  - A similar shut-down system, as in the first years of the VENUS facility (VULCAIN-project), based on shut-down rods, will have to be installed.
  - Construction of fuel assemblies (lead + fuel rodlets) for the core and lead for the reflector --> 30 t lead
  - Possible support structure to reinforce the structures to carry the lead
  - The scram logic remains almost the same, only the shut-down action changes from fast water dump to safety rod drop



#### GENEPI accelerator of CNRS



- 1) High Voltage Head,
- 2) duoplasmatron,
- 3) accelerator tube,
- 4) quad Q1,
- 5) magnet,
- 6) quad Q2,
- 7) quad Q3,
- 8) quad Q4 + T2 part,
- 9) MASURCA tube,
- 10) target





# GENEPI needed modifications to existing GENEPI 1-2

- The duoplasmatron source used at the present time is designed for a pulsed use and has to be changed to work in continuous mode.
- Beam interruption operation will have to implemented by driving the source itself
- The focusing structure has to be redesigned for the whole intensity range required now (intense for pulsed mode and less intense in continuous mode).
- The pulsed source (or a continuous of 160  $\mu$ A) gives a maximum power on the target to be evacuated around 40 W. The cooling is ensured by a compressed air flow. At max 1 mA beam, the power to be evacuated is 250 W. The performances of the cooling system have then to be improved (without oil or water), which does not seem to be a major problem.
- The monitoring and control system of GENEPI 1-2 is performed by a PC computer and electronics which are based on out of date items (dates from 1998). A completely new system based on modern components and techniques has to be studied.



## "GUINEVERE" critical configuration








## Fuel (assembly) characteristics

- Fuel rodlets provided by CEA
  - > U-metal
  - Enrichment 30 %
  - Diameter = 1,27 cm
  - ➤ Length= 20 cm
- Lead rodlets from CEA or lead blocks
- Fuel assembly
  - > 60 cm active length in height
  - > About 10 cm in lateral dimension






## "GUINEVERE" critical configuration

- Basic critical configuration
  - > Two fuel loading assembly types (9/25 & 13/25)
  - > With fuel rods of 1.27 cm diameter, 60 cm, 30% U-metal
  - > Equivalent diameter of core 100 cm
  - Radial lead reflector of about 30 cm, top lead reflector of 40 cm and a bottom lead reflector of 40 cm
  - > configuration contains 2460 rods
  - $> k_{eff} = 1,0071 \pm 0.0005$
  - Total mass is about 1200 kg (360 kg U-235)




## Core Lay-out








## Fuel Assembly Design






# Additional supporting structure to carry the lead in the vessel

 Calculations have demonstrated that the additional supporting structure is sufficient









## ፲፫٠ ር፫፮፮ Shut-down system based on safety rods


 8 absorber rods symmetrically placed at the interface core-reflector






#### Coupling of accelerator to VENUS (1)








### Coupling of accelerator to VENUS (2)





### Natural air cooling

 Calculations with pessimistic equivalent heat conductivity for the fuel assembly





#### Main keydates in the planning

- Stop of VENUS reactor: 1-4-2007
- Design of fuel assembly: 1-4-2007
- Removal of internal parts of VENUS: 1-7-2007
- Design of core: 1-7-2007
- Transport of fuel from CEA to SCK-CEN: 1-1-2008
- Fuel assembly construction: 1-7-2008
- Accelerator room construction: 1-1-2008→1-7-2008
- Installation new components in VENUS: 1-12-2008
- Commissioning installation: 1-1-2009

  →1-7-2009
- Transfer of GENEPI from CNRS to SCK-CEN: 1-5-2009
- Start of experiments: 1-9-2009



# Objective of the experimental programme

- Characterisation of the reference core SCO
  - > Reference to the critical state
- Reactivity measurements in subcritical cores
  - > SC1 (0.97), SC2 (0.95), SC3 (0.985)
  - Current-to-flux measurements
    - Static measurements
    - Kinetic measurements

$$-\rho = c\varphi * \frac{S}{R}$$

$$S = source \ neutrons / s = \frac{I}{e} N_{neutrons/ion}$$


$$R = \varepsilon \Sigma_d \Phi_d V_d$$


- Interim cross-checking techniques at beam interruptions
- Reactivity calibration techniques
  - ♣ Mainly Pulsed Neutron Source techniques



# Interim cross checking techniques at beam interruptions

- This part of the programme requires to pilot the source in a continuous mode with short and prompt beam interruptions repeated several times
- 2 techniques are planned to be applied at beam trips (separately):
  - > prompt decay fitting techniques
    - fitting of the prompt population decay (expo) or its decrease rate (kp) after the source interruption
    - ♣ Highly depends on the spectrum conditions of the core → fast core is needed








# Interim cross-checking techniques at beam interruptions

- Prompt Jump Techniques
  - $\triangleright$  Reactivity determination based on the measurement of P<sub>H</sub>, P<sub>C</sub> and P<sub>L</sub>





#### Conclusions

The GUINEVERE-project will provide a unique experiment with a continuous beam coupled to a fast (sub)critical assembly allowing full investigation of the methodology of reactivity monitoring for XT-ADS and EFIT.