Why do large construction projects always perform badly? The MEGAPROJECT experience

Professor Naomi Brookes

Chair – MEGAPROJECT COST Action University of Leeds, UK

Dr Giorgio Locatelli

WG Leader – MEGAPROJECT COST Action University of Lincoln, UK

1

Megaproject

Aims of the Session

- To place the performance of European nuclear new build megaprojects in the context of other European megaprojects
- To highlight the megaprojects characteristics that are associated with megaproject performance
- To understand the implications for Nuclear Megaprojects



What is a Megaproject?

Megaprojects are extremely large-scale investment projects typically costing more than € 0.5 billion. Megaprojects include powerplant (conventional, nuclear or renewable), oil and gas extraction and processing projects and transport projects such as highways and tunnels, bridges, railways, seaports and even cultural events such as the Olympics. Megaprojects are united by their **extreme complexity** (both in technical and human terms) and by a long record of **poor delivery**.







3

Megaproject

MEGAPROJECT - The Effective Design and Delivery of Megaprojects in the European Union


- A network of ~80 researchers from 22 European countries
- Funded under the auspices of the ESF COST Action programme by the European Commission
- Looking at what can be learnt across sectors
- Started May 2011. Current funding until 2015.























Relating megaproject characteristics and meagproject performance Protocol 1. Delineation of ~50 megaproject characteristics (independent variables binary in nature) 2. Simple expression of megaproject performance against time and cost(dependant variables in binary nature) 3. Capture both of the above in an excel matrix 4. Perform statistical analysis (Fisher exact test) 5. Analyse the results.







Whole megaproject population findings

- Very few characteristics have statistically significant relationships
- Energy megaprojects have a completely different pattern of relationships than transport megaprojects apart from:
 - The effect of using SPEs in governance
 - Modularity (plant level and site level)







Megaproject				
1814	Category	Independent Variables	Correlating with	strength of association
1	Modularity	Project is modular	delay in planning on budget on-time construction	80% 89% 89%
2	Regulatory Environment	Project has a strong regulatory environment	on-time planning over budget delay in construction	83% 80% 80%
3	External Stakeholder Interactions	No protest at a local level	delay in construction over budget	86% 86%
T. C. Succession of the Contract of the Contra	Governance	The project uses an SPE structure	delay in planning on-time construction	90% 88%

Characteristics that could help nuclear megaproject performance (in the long run)

- SPEs
- Modularity

Characteristics that could hinder megaproject performance (in the long run)

- strong regulatory environments: "learn how to build what it has been designed"

